BILL OF MATERIALS

BOM Document - Bom_test_sync_EngrAlex_serverx

DEPARTMENT	PROJECT	LOCATION	DATE
Design and Construction Department	PROPOSED TOMSWORLD RECREATION CENTER	Pasig City Metro Manila	2026-02-14

Department: Design and Construction Department
Project Name: PROPOSED TOMSWORLD RECREATION CENTER
Location: Pasig City Metro Manila
Total Floor Area: 14400
Date: 2026-02-14

BILL OF MATERIALS

MATERIALS COST ESTIMATE: BILL OF MATERIALS SECTION

PANEL BOARD AND CIRCUIT BREAKERS:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
Main 1-30A G.E. TYPE, 60Hz, Bolt-on Type,With Safety ENCLOSURE	pcs	1	1,600.00	1,600.00
Main 1-20A G.E. TYPE, 60Hz, Bolt-on Type,With Safety ENCLOSURE	pcs	1	1,200.00	1,200.00
MDP(MAIN DISTRIBUTION PANEL): Main: 1 - 200A, THREE PHASE, SE-EZC100H3200, 3P, 400V, 65 KAIC MCCB , SCHNEIDER, w/ Ground and neutral bus terminal. Branches: 1- 100AT/100AF, SE-EZC100N3100, 3P, 10KAIC, 400V, 60Hz, Bolt-on Type, 1- 40AT/100AF, SE-EZC100N3040, 3P, 14KAIC, 400V, 60Hz, Bolt-on Type, SCHNEIDER Brand w/ Ground and Neutral busbar terminal. NEMA 1 ENCLOSURE	assy	1	120000	120,000.00

WIRES AND CABLES:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
3.5 sq. mm. THHN, Phelps Dodge	box	1	5,800.00	5,800.00
5.5 sq. mm. THHN, Phelps Dodge	box	1	5,800.00	5,800.00

LIGHTING FIXTURES:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
12" Diammeter Domelight Honey Comb Reflctor with E27Base 26watts LED BULB	box	1	5,800.00	5,800.00
18 Watts GE Downlight 8" Diameter Round Warmwhite	box	1	5,800.00	5,800.00

AUXILIARY LIGHTING FIXTURES:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
ESP32 Microcontroller with Headers	box	1	5,800.00	5,800.00
ESP32 Expansion Board	box	1	5,800.00	5,800.00

CONVENIENCE OUTLET AND SWITCHES:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
GROUNDING DUPLEX, UNIVERSAL OUTLET w/ safety shutter, 250V VAC, 15AMP, IP64, WITH PLATE AND COVER PANASONIC BRAND	sets	35	240.00	8,400.00
Floor Outlet 2 GANG, ABSO BRAND	set	35	30.00	1,050.00

CONDUIT AND FITTINGS:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
15mm diam. Emt Pipe	pc	35	240.00	8,400.00
20mm diam. Emt Pipe	pc	35	30.00	1,050.00

MISCELLANEOUS:

ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
Electrical Tape	pcs	6	50.00	300.00
Rubber Molding	box	2	5,000.00	10,000.00
Electrical Fixtures circuit at 1/2-10am	pc	1	200.00	200.00
Flexible hose connector clamp 1/2	pcs	80	15.00	1,200.00
Duct Tape	pcs	5	200.00	1,000.00
Warning Tape	pcs	10	250.00	2,500.00
Cloth Tape	pcs	5	250.00	1,250.00

TOTAL ESTIMATED COSTS:	**192,950.00**

PREPARED BY:	CHECKED BY:	CHECKED AND APPROVED BY:	CHECKED AND APPROVED BY:
Johny Austria Electrician in-charge	**Kimberly Onin** Accounting Department	**Edison Sing** Logistics/Warehouse Dept. Head	**Ryan Caguioa** DAC Department HEAD
NOTED AND APPROVED BY:	**APPROVED BY:**	**APPROVED BY:**	**APPROVED BY:**
Alexander Fernandez Electrical Engineer	**Ronal Lopez** Division HEAD	**Racquel De Lara** AVP-OPERATIONS NVI/B	**Oliver Ryan Co** VP-Corporate Management